JF-2MED
(MASTER STATION)

JF-2HD
(SUB MASTER STATION)

CALL   PLAY   REC   MENU

MONITOR

TALK

CALL   PLAY   REC   MENU

MONITOR

TALK

SEE NOTE 2

SEE NOTE 2

RECEPTION DESK

TO CCTV HEADEND
FOR RECORDING VIDEO
SIGNALS

RECEPTION DESK

JF-DVF-HID (FLUSH)
(DOOR STATION)

JF-DVF-HID (FLUSH)
(DOOR STATION)

MAIN ENTRANCE

REAR ENTRANCE

SEE NOTE 2

RY-3DL
(SELECTIVE DOOR
RELEASE
ADAPTOR)

PS-1820UL
(POWER SUPPLY)

(ELECTRIC STRIKE)
MAIN ENTRANCE

(ELECTRIC STRIKE)
REAR ENTRANCE

SBX-LSE
(SECURITY
LOCK BOX)

NOTES:

1. RISER DIAGRAM ABOVE IS DIAGRAMMATIC AND IS SHOWN TO PROVIDE A GENERAL OVERVIEW OF MAJOR SYSTEM COMPONENTS AND
    INTERCONNECTIONS. THIS DIAGRAM IS NOT TO BE USED FOR FIELD INSTALLATION PURPOSES.

2. ALL WIRING SHALL BE IN CONDUIT, 1" MINIMUM. WIRING SHALL BE PROVIDED ACCORDING TO THE MANUFACTURER'S INSTRUCTIONS.

3. PROVIDE ALL ANCILLARY COMPONENTS, HARDWARE, POWER CONNECTIONS AND WIRING AS REQUIRED FOR COMPLETE AND OPERATING DOOR
    INTERCOM SYSTEM.

4. SYSTEM SHALL BE AS MANUFACTURED BY AIPHONE:
    A. HANDSFREE MASTER STATION: MODEL JF-2MED.
    B. HANDSFREE SUB MASTER STATION: MODEL JF-2HD.
    C. DOOR INTERCOM STATION: MODEL JF-DVF-HID.
    D. SELECTIVE DOOR RELEASE ADAPTOR: MODEL RY-3DL.
    E. POWER SUPPLY: MODEL PS-1820UL.
    F. BACKBOX: MODEL SBX-DVF SHALL BE INSTALLED WHEN BRICK WALL IS INDICATED.
    G. SECURITY LOCK BOX: MODEL SBX-LSE SHALL BE INSTALLED FOR AFTER HOURS LOCK DOWN. ONE LOCK BOX PER DOOR STATION.

5. CONTACT AIPHONE COMMUNICATIONS (800) 692-0200 FOR FURTHER INFORMATION.

CHICAGO PUBLIC SCHOOLS
CAPITAL IMPROVEMENT PROGRAM
INFORMATION TECHNOLOGY SERVICES
INFRASTRUCTURE STANDARDS
DOOR INTERCOM DETAIL
2 DOOR DETAIL — RENOVATION

			DESIGNED CPS			SHEET NO.
			DRAWN CPS			
			CHECKED CPS	PROJECT NUMBER	SCALE NONE	ED.821
1	10/25/11	DVS RACK #5	APPROVED CPS		DATE 07/23/14	
NO.	DATE	REVISION	BY			