

NOTES:

- 1. PROVIDE AN AUDIOVISUAL 14" TALL x 14" WIDE x 3.5" DEEP ENCLOSURE MOUNTED BEHIND THE DISPLAY WITH KNOCKOUTS FOR POWER, DATA AND HDMI OUTLETS.
- 2. THIS PROVISION APPLIES ONLY TO ADMINISTRATIVE OFFICE SITES.
- 3. PROVIDE DEVICES AS SHOWN AT TABLE TOP. COORDINATE WORK WITH FURNITURE PROVISIONS.
- 4. PROVIDE CONDUIT FROM FLOOR TO DISPLAY ENCLOSURE. SIZE CONDUIT TO ACCOMMODATE CABLING FOR ALL DESIGNATED SYSTEMS.
- 5. PROVIDE FLOOR ACTIVATION POINT TO FEED ALL RESPECTIVE DEVICES AT TABLE TOP. COORDINATE EXACT REQUIREMENTS WITH CPS.
- 6. DATA OUTLET FOR TOUCHSCREEN AUDIO VISUAL CONTROL. COORDINATE WITH CPS WHETHER AN RS485 OR AN ETHERNET CONNECTION IS REQUIRED.
- 7. FULL MOTION/RANGE ARTICULATING WALL TV MOUNT, PROVIDED BY OTHERS. INSTALLATION NOT TO EXCEED 4-INCH DEPTH UNLESS CANE DETECTION IS PROVIDED. RALLY BAR SHALL BE MOUNTED ABOVE THE TV DISPLAY.
- 8. THIS DETAIL INCLUDES SYSTEM INFRASTRUCTURE FOR EQUIPMENT PROVIDED BY OTHERS. REFER TO RESPECTIVE EQUIPMENT PROVIDED BY OTHERS. REFER TO RESPECTIVE AV SYSTEM SCOPE DATA

SHEETS, ELEVATION AND WIRING DIAGRAM DETAILS. EXACT REQUIREMENTS SHALL BE COORDINATED WITH CPS.

9. THIS PROVISION APPLIES ONLY TO SCHOOL FACILITIES.

Chicago PUBLIC SCHOOLS
Schools

CAPITAL IMPROVEMENT PROGRAM
INFORMATION TECHNOLOGY SERVICES
INFRASTRUCTURE STANDARDS

SMALL CONFERENCE ROOM - MAXIMUM 6 SEATS

_									
					DESIGNED				SHEET NO.
					CPS				
					DRAWN				
					CPS				ED.340A
					CHECKED	PROJECT NUMBER	SCALE	DATE	[D.5707]
					CPS				
					APPROVED		NONE	05/30/25	
	NO.	DATE	REVISION	BY	CPS				