




**CHICAGO PUBLIC SCHOOLS**  
**CAPITAL IMPROVEMENT PROGRAM**  
**INFORMATION TECHNOLOGY SERVICES**  
**INFRASTRUCTURE STANDARDS**  
**TYPICAL CLASSROOM TEACHING WALL**  
**(NEW CONSTRUCTION)**

NO.	DATE	REVISION	BY	DESIGNED CPS	PROJECT NUMBER	SCALE NTS	DATE 03/23/18	SHEET NO. ED.301A
				APPROVED CPS				

**NOTE**

- FOR ALL WORKSTATION LOCATIONS SHOWN WITH A RECEPTACLE AND AN ASSOCIATED TELE/DATA DEVICE OR HDMI CONNECTION, PROVIDE A COMBINATION BACKBOX WITH A COMMON COVER. WALL BOX SHALL BE A TWO, THREE, OR FOUR GANG BACKBOX WITH A DIVIDER, IN ORDER TO ACCOMMODATE THE POWER AND DATA. BACKBOX SHALL BE THE WALLSOURCE BACKBOX AS MANUFACTURED BY WIREMOLD OR EQUIVALENT. PROVIDE ALL NECESSARY ACCESSORIES AS REQUIRED FOR A COMPLETE INSTALLATION.
- BACKBOXES SHALL BE OFFSET AND NOT MOUNTED BACK TO BACK.

REFER TO DETAIL ED.806

**FOR TO COORDINATE CEILING HEIGHT AND RESOLVE ANY CONFLICTS**